

15-047-00098-0000

Form CP-3
Rev. 6-26-62

24
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 17 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Inger Oil Company

Complete Address: 1020 Central Bldg., Wichita, Kansas

Lease Name Wilson Well No. # 1

Location SE SE SE Sec. 34 Twp. 25 Rge. 16 (E) (W) W

County Edwards Total Depth 4485

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 11:45AM Day 15th Month Jan. Year 1964

The Above well was plugged as follows:

408' of 8 5/8" surface pipe, cement circulated. 4485' of 5 1/2" long string,
cemented with 200 sacks. Top perferation 4402'. Bottom of hole was sanded
to 4390', and cemented with 5 sacks. Fluid was up in hole and would not
bail down. Plug was pushed to 275', and 10' rock bridge. 5 sacks cement
was mixed in barrel and put on plug through dump bailer, and let set over
night. Next morning hole bailed down and 20 sacks cement was added to plug.
Hole was filled with mud to 40', 10' rock bridge, cemented with 10 sacks
to base cellar. 3270' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/17/64

INV. NO. 8471-W

Signed: Archie Elving
Well Plugging Supervisor