

15-047-10115-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 18 1964
11-18-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Santa Fe Pipe & Supply Inc.

Complete Address: P. O. Box 562, Great Bend, Kansas

Lease Name Mayhew Well No. # 3

Location C SE NW Sec. 34 Twp. 25 Rge. 16 (E) (W)W

County Edwards Total Depth 4500'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 2:30PM Day 16th Month Nov. Year 1964

The Above well was plugged as follows:

396' of 8 5/8" surface pipe, cemented with 275 sacks. 4496' of 4 1/2" long
string, cemented with 100 sacks. Bottom of the hole was sanded to 4450',
and cemented with 3 sacks. Fluid level was up in the hole. Bridge plug
was pushed in fluid to 275', and 10' of rock bridge on plug. 4 sacks of
cement with 5% Calcium Chloride was mixed in barrel, and put on plug at
265', through the dump bailer. And let set over-night. Next morning hole
was bailed dry, and 21 sacks of cement was added to the plug. Hole was
filled with mud to 40', and 10' of rock bridge, and cemented with 10 sacks
to the base of the cellar. 3395' of 4 1/2" long string was recovered from the hole.
I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 11/18/64

INV. NO. 189-W

Notice-

Correction of Location

Archie Elving