

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

DEC 12 1962

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Inger Oil Company

Complete Address: 1020 Central Bldg. Wichita, Kansas

Lease Name Giles Well No. 1

Location CNW NE Sec. 34 Twp. 25 Rge. 11 (E) (W)

County Edwards Total Depth 4488

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: KnighT Casing Pulling Co.

Address: Chase, Kansas License No. 436

Operation Completed: Hour \_\_\_\_\_ Day 30 Month 11 Year 1962

The Above well was plugged as follows:

Checked hole to 4488'. Sanded to 4400'  
and dumped 5 sacks of cement @ 4400' with  
dump bailer. Pulled 5 1/2" casing. Muddled  
hole to 310'. Set Rock Bridge to 300' and ran  
20 sacks of cement @ 300'. Muddled to 40' &  
set rock bridge to 30' and ran 10 sacks of  
cement to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/12/62

INV. NO. 6208-u

Signed: Dill Lackamp  
Well Plugging Supervisor  
by S. S. Greider