

15-047-20454-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 27 1979

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

CONSERVATION DIVISION
Wichita, Kansas
(of this well)

API Number 15 - -

Operator's Full Name Derrick Petroleum, Inc.

Complete Address 1445 Sierra Drive, Wichita, Ks. 67209

Lease Name Gibson Well No. 1

Location NE SE NE Sec. 34 Twp. 25 SRge. 16 (E) (W) X

County Edwards Total Depth 4518

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase, Ks. 67524 License No. 683


Operation Completed: Hour 12: N Day 26 Month 3 Year 1979

The above well was plugged as follows:

452' 8 5/8" casing. 4 1/2" casing set @ 4516' w/ 150 sax cement.
Plug back to 4410'-Top pref.. @ 4365'- Sand back to 4340' top sand
w/ 4 sax mixed cement w/ dump bailer. Pull 3400' 4 1/2" casing. Allied
mixed & pumped 5 sax hulls-25 sax mud-release plug-mixed & pumped
135 sax 50/50 posmix cement w/ 4% gel & 4% c.c. to top of casing.
Shut in w/ 300# pressure.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: 
Well Plugging Supervisor

DATE 3-28-79
NO. 9311-U