

15-047-10142-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 29 1963
8-29-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Inger Oil Co.

Complete Address: 1020 Central Bldg., Wichita, Kansas

Lease Name Wilson Well No. # 1

Location NW NW SE Sec. 34 Twp. 25 Rge. 16 (E) (W)W

County Edwards Total Depth 4525

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 4:30PM Day 24th Month August Year 1963

The Above well was plugged as follows:

380' of 8 5/8" surface pipe, cemented with 225 sacks. 4525' of 5 1/2" long
string, cemented with 100 sacks. Plugged back to 4380'. Top perforation
4358'. Sanded to 4340', cemented with 5 sacks. Hole was bailed down to
275'. Plug was set at 275', 10' rock bridge, cemented with 20 sacks.
Hole was filled with mud to 40', 10' rock bridge, cemented with 10 sacks
to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 8/29/63
INV. NO. 9663-4