

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

MAY 25 1964

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Skelly Oil Co.

Complete Address: Box 649 Mc/Cook, Nebraska

Lease Name Anna Koehn Well No. # 1

Location C NW SW Sec. 22 Twp. 32 Rge. (E) (W) 30

County Meade Total Depth 5685'

Abandoned Oil Well x Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Ace Pipe Pulling Co.

Address: Great Bend, Kansas License No. 2

Operation Completed: Hour 5 PM Day 21 Month 5 Year 64

The Above well was plugged as follows:

8 5/8"-1428' Circulated w/cement. 5 1/2"-5684' Cemented.

Plug back to 5567' Top perforations 5551'

Plug bottom w/sand to 5540' 20 Sax.cement 5540' to 5380'

Mud 5380' to 700' Spotted 35 Sax.cement 700' to 600'

Mud 600' to 45' Plug, 15 Sax.cement 45' to 0'

Company Pump. Pulled 2685' 5 1/2" Pipe.

Cut surface pipe off 5' below ground level.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 5/26/64

INV. NO. 9216-W