

15-007-01171-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

APR 6 1967

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza Bldg., Wichita, Kansas

Lease Name McKeever Well No. # 1

Location NE SW NE Sec. 20 Twp. 32 Rge. 10 (E) (W) W

County Barber Total Depth 4434'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 9:30AM Day 4th Month April Year 1967

The Above well was plugged as follows:

160' of 8 5/8" surface pipe, cemented with 130 sacks. 4434' of 5 1/2" long
string, cemented with 125 sacks. Plug back T.D. 4425'. Top perferation
4415'. Bottom of the hole was sanded to 4350', and cemented with 5 sacks,
through the dump bailer. 3600' of 5 1/2" long string was recovered from the
hole. Hole was squeezed. 10 sacks of Gel-Mud and 75 sacks of cement was
pumped into the surface pipe, through an 8 5/8" swage, to a pressure of
350 lbs. A wiping plug was run betwwen the Gel-Mud and the cement.

This cementing was done by Globe Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 4/6/67
INV. NO. 5006-w