


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Reno County. Sec. 21 Twp. 25S Rge. (E) 6 (W)

Location as "NE/CNW/SW" or footage from lines S/2 SW SW  
Lease Owner Okmar Oil Company  
Lease Name HORNBAKER Well No. 1  
Office Address 1130 Wichita Plaza, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 30, 1968  
Application for plugging filed 19\_\_\_\_  
Application for plugging approved 19\_\_\_\_  
Plugging commenced August 30, 1968  
Plugging completed August 30, 1968  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Hugh Scott of McPherson)

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4055 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	330'	8-5/8"	8/21/68	-----
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy Mud from Total Depth to 300 Feet;  
Plug and 25 sax Cement thru the Drill  
Pipe; Mud to 40 Feet, 1/2 sax Halls, Plug  
bridged with Kelly and 10 sax Cement to  
Base of Cellar; 2 sax Cement in Rat Hole.  
Job completed @ 4:00 A.M. on 8/30/68.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 4 1968  
CONSERVATION DIVISION  
Wichita, Kansas

9-4-68

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Sage Drilling Co.  
Address 500 Bitting Building, Wichita, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Wayne W. Kahmeyer of Sage Drilling Co. (Employee of owner) or (owner or operator) of the above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne W. Kahmeyer  
500 Bitting Building, Wichita, Kansas (Address)

Sworn to before me this 3rd day of September, 1968

Louise K. Whitted  
Louise K. Whitted = Notary Public.

My commission expires November 26, 1970.



DRILLERS LOG

HORNBAKER NO. 1

CASING RECORD:	OPERATOR: Okmar Oil Company	DESCRIPTION:
8-5/8" @ 330' w/200 sax cement	CONTRACTOR: Sage Drilling Co.	S/2 SW SW Sec. 21-25S-6W Reno County, Kansas
TOTAL DEPTH: 4055'	COMMENCED: August 21, 1968	ELEVATION: 1544KB
	COMPLETED: August 30, 1968	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	15	
Red Bed	15	175	
Blue Shale	175	410	
Shale & Shells	410	1095	
Anhydrite	1095	1122	
Shale & Shells	1122	1400	
Shale & Lime	1400	1860	
Lime & Shale	1860	2600	
Shale & Lime	2600	2940	
Lime & Shale	2940	3069	
Shale & Lime	3069	3188	
Lime & Shale	3188	3475	
Lime, Shale & Chert	3475	3615	
Chert & Shale	3615	3688	
Mississippi Lime	3688	3745	
Lime, Chert & Shale	3745	3790	
Lime, Shale & Chert	3790	3906	
Shale & Lime	3906	3965	
Lime & Shale	3965	4018	
Shale & Sandy Lime	4018	4055	D&A

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 4 1968  
CONSERVATION DIVISION  
Wichita, Kansas

9-4-68

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Wayne W. Kahmeyer  
Wayne W. Kahmeyer



Subscribed and sworn to before me this 3rd day of September, 1968.

Louise K. Whitted  
Louise K. Whitted, Notary Public

My commission expires:  
November 26, 1970.