


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

15-155-00342-0000

NORTH



Locate well correctly on above
Section Plat

Reno County, Sec. 25 Twp. 25 Rge. (E) 6 (W)
Location as "NE/CNW/SW" or footage from lines NE NE NW
Lease Owner Rupp-Ferguson Oil Co.
Lease Name Rogers Well No. 1
Office Address 523 Petroleum Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-20-54 19
Application for plugging filed 4-20-54 19
Application for plugging approved 4-20-54 19
Plugging commenced 4-20-54 19
Plugging completed 4-20-54 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel E. Durkee
Producing formation Depth to top Bottom Total Depth of Well 4035 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	265	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Ran half drill pipe in hole. Layed down. Ran second half drill pipe. Gunned pits. Circ. heavy mud. Layed down drill pipe. Filled hole w/mud to 255. Built bridge of hulls - plug - rocks to hold 9 joints drill pipe. Mixed 15 sacks cement. Put thru 8 joints drill pipe. Filled hole w/mud to 30'. Hulls - plug (plug tied). Mixed cement. Filled to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

APR 24 1954
CONSERVATION DIVISION
Wichita, Kansas

4-24-54

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rupp-Ferguson Oil Co.
Address 523 Petroleum Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. W. Knox

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature)

523 Petroleum Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of April 19 54

My commission expires 6-4-55

Notary Public.



CONTRACTOR'S WELL LOG

ROGERS #1
NE NE NW, Sec. 25-25S-6W
Reno County, Kansas

Total Depth 4035'
Ran 265' of 8 5/8" surface casing,
cemented with 200 sacks.

Commenced 4-4-54
Completed 4-20-54
Contractor: Rupp-Ferguson Oil Co.

D. & A.
Elevation 1451 A.B.

Figures Represent Bottom of Formation

170	surface hole
266	shale & rock
480	shale & shells
770	shale & salt
940	lime
1125	lime & shale
1240	lime
1415	shale & shells
1540	lime & shale
1600	lime
1710	lime & shale
2115	shale & shells
2644	shale & lime
2755	shale & sandy lime
3493	chert
3685	cherty lime
3715	lime
3877	shale
3895	lime, shale & chert
3952	lime, shale & sand
4025	lime & shale
4033	lime
4035	T.D.

<u>Tops:</u>	
Br. Lime	2774
Lansing	2799
Miss.	3487
Kinderhook	3850
Chattanooga	3858
Viola	3877
Simpson Sand	3911
Arbuckle	4003

Drill Stem Test -
3489-93
Open 1 hr.
Recovered 150' salt water.
B.H.P. 1200#.

RECEIVED
STATE CORPORATION COMMISSION

APR 27 1954

CONSERVATION DIVISION
Wichita, Kansas

4-27-54

STATE OF KANSAS)
) SS:
SEDGWICK COUNTY)

I, L. W. Knox, Landman for Rupp-Ferguson Oil Co., do hereby
certify that the above and foregoing is a true and correct copy of the
contractor's well log of the Rogers #1 well in the NE NE NW, Sec.
25-25S-6W, Reno County, Kansas.

L. W. Knox

Subscribed and sworn to before me this 21st day of April, 1954.

Helen Vorine
Notary Public

My Commission Expires 6-4-55

