

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Reno County, Sec. 23 Twp. 25 Rge. 7 (BX) (W)

Location as "NE/CNW&SW" or footage from lines NE NE SE

Lease Owner Harold Kottwitz

Lease Name Clayton Well No. 1

Office Address 2501-10th St. Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed 4-6 19 56

Application for plugging filed 4-6 19 56

Application for plugging approved 4-6 19 56

Plugging commenced 4-6 19 56

Plugging completed 4-6 19 56

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee, Box 597, McPherson, Ks.

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	265.40	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole mudded to 260'. Set wooden plug and cemented with 15 sacks of cement. Second plug set at 25' and cemented with 5 sacks of cement.

APR 17 1956 4-17-56

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Welch & Olsson Drilling Co. Inc.

Address 203 Rule Bldg. Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. R. E. Welch


(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature] 203 Rule Bldg. Wichita, Ks. (Address)

SUBSCRIBED AND SWORN TO before me this 13th day of April, 19 56

[Signature] Edith Erker Notary Public.

My commission expires June 12, 1959



WELL LOG.

OWNER: Harold Kottwitz,

Elevation: 1490 R.B.

CONTRACTOR: WELCH &amp; OLSSON DRILLING CO. INC.

Comm. Drlg: 3-27-56

CLAYTON #1

Compl. " 4-6-56

NE NE SE of Sec. 23-25-7W, Reno County, Kansas.


Production: D &amp; A

Casing Record.

Set 265.40' of 8 5/8" with 200 sacks of cement.

(Figures indicated bottom of Formations.)

<u>FORMATIONS</u>	<u>DEPTHS</u>	<u>FORMATION TOPS.</u>
Sand:	60	Heebner: 2790 (-1300)
Red Bed:	290	Toronto: 2807 (-1317)
Anhydrite:	315 ?	Douglas: 2815 (-1325)
Shale & Sand:	670	Brown Lime: 2992 (-1502)
Anhydrite:	680	Lansing: 3022 (-1532)
Shale & Shells W/salt:	750	Marmaton: 3379 (-1889)
Salt:	890	Cherokee Shale: 3586 (-2096)
Shale & Shells:	965	Mississippi: 3705 (-2215)
Shale & Shells W/Lime		Kinderhook Shale: 3842 (-2352)
Stks:	1095	Misener Sand: 4046 (-2556)
Shale & Lime:	1540	Viola: 4054 (-2564)
Shale & Shells W/Lime		Simpson Shale: 4070 (-2580)
Stks:	1655	Simpson Sand: 4086 (-2596)
Shale & Shells:	1800	Arbuckle: 4159 (-2669)
Shale & Shells:	2065	
Shale & Shells & Sand:	2200	
Shale & Shells:	2500	
Shale & Shells W/Lime		
Stks:	2720	
Shale W/Lime Stks:	2825	
Sand:	3035	
Lime & Shale:	3108	
Lime:	3245	
Lime, Shale & Chert;	3300	
Lime:	3435	
Lime & Shale:	3515	
Lime:	3580	
Lime & Shale:	3650	
Lime & Shale:	3710	
Chert:	3790	
Lime W/shale:	3825	
Chert W/Lime:	3836	
Shale:	4046	
Sand:	4054	
Lime:	4055	
Limestone:	4070	
Shale:	4086	
Sandstone:	4160	
Lime:	4175 T.D.	



4-17-56

STATE OF KANSAS, SEDGWICK COUNTY, KANSAS:

I hereby certify that the above is a true and correct copy of Drillers Log of well drilled in the NE NE SE of 23-25-7W, Reno County, Ks.

WELCH &amp; OLSSON DRILLING COMPANY, INC.

BY

R. E. WELCH

Subscribed and sworn to before me this 13th day of April, 1956

My commission expires: 6-12-59

Edith Erker, Notary Public.