

STATE OF KANSAS
STATE CORPORATION COMMISSION
90 Colorado Derby Building
Chicago, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-155-21323-0000

LEASE NAME STULL

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1-3

3070 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 3 TWP. 25 SRGE. 8W (E) or (W)

COUNTY RENO

LEASE OPERATOR Stelbar Oil Corporation, Inc./Grand Mesa
Operating Co., Inc.

ADDRESS 155 N. MARKET, STE #500

PHONE# (316) 264-8378 OPERATORS LICENSE NO. #6044/#9855

Date Well Completed 07-25-94

Character of Well D&A

Plugging Commenced 3:00 PM

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4:30 PM

The plugging proposal was approved on 07-20-94 (date)

by Doug Louis (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 4070'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	231	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, -from ___ feet to ___ feet each set

Heavy mud to 1200' with 35 sacks, heavy mud to 280' with 35 sacks, 25 sacks 60' to surface, 15 sacks in rat hole.

Name of Plugging Contractor STERLING DRILLING COMPANY License No. 5142

Address P O BOX 129, STERLING KS 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: STEBLAR OIL CORPORATION INC.

STATE OF KANSAS COUNTY OF RICE, ss.

LEONARD D. DETTER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Leonard D. Detter
Leonard D. Detter

(Address) P O BOX 129, STERLING KS 67579

RECEIVED
STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 27th day of July, 19 94

AUG 24 1994
Cheryl R. Davis
Notary Public

USE ONLY ONE SIDE OF EACH FOR CONSERVATION DIVISION
WICHITA, KANSAS



Form CP-1
Revised 05-88

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

(316) 278-2131

SAMPLE LOG ----- STULL #1-3

Located: 3070' FSL & 2970' FEL of Sec. 3-25S-8W, Reno County, Kansas

OWNER: STELBAR OIL CORPORATION INC

ROTARY DRILLING CONTRACTOR: STERLING DRILLING COMPANY

COMMENCED: July 19, 1994

COMPLETED: July 25, 1994

TOTAL DEPTH: 4070' Driller
4070' Logger

LOG

0' - 68' Surface Soil and Sand
68' - 235' Red Bed
235' - 590' Red Beds and Shale
590' - 1270' Shale
1270' - 4070' Lime and Shale

CASING RECORD

Spud at 7:15 AM, 07-19-94. Drilled 235' of 12 1/4" hole. Ran 5 joints 8 5/8" 20# casing. 219.65' pipe set at 231' K.B. Cemented with 200 sacks 60/40 Pozmix with 2% gel and 3% cc. Plug down at 11:00 AM, 07-19-94 by Allied. Good returns. Ticket No. 6575.

Plugged.

DEVIATION SURVEY

3/4° @ 230'
3/4° @ 3750'
1° @ 4070'

RECEIVED
STATE CORPORATION COMMISSION

AUG 24 1994
CONSERVATION DIVISION
WICHITA, KANSAS

8-24-94