

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Reno SEC. 36 TWP. 25S RGE. 5W E/W
Location as in quarters or footage from lines:
NW NE

Locate Well
correctly on above
Section Platt.

Lease Owner KRWX Kelso Casing Pulling
 Lease Name Beltz #1 Well No. _____
 Office Address Box 176, Chase, Ks. 67524
 Character of Well (Completed as Oil, Gas or Dry Hole): RECEIVED
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 7/7/81
 Plugging completed 7/13/81
 Reason for abandonment of well or producing formation Depleted

STATE CORPORATION COMMISSION
 7-16-81
 CONSERVATION DIVISION
 Wichita, Kansas

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation _____ Depth to top _____ bottom T.D. 4220'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				10-3/4"	262'	None
				7"	4218	2657'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved onto location. Pulled 19" stretch. Ran sand to 4150' and set 7 sacks cement. Made shots at 2850, 2763 and 2660. Pulled total of 60 joints. Set rock bridge from 300' to 285' and ran 6 yards ready mix cement. Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of July, 19 81

My Commission expires:



Joan Kelso
Notary Public.

15-155-20568-0000

Schlumberger

DUAL INDUCTION - LATEROLOG

COUNTY RENO
 FIELD WILDCAT
 LOCATION 36-25S-5W
 WELL BELTZ 1
 COMPANY PLAINS RESOURCES

COMPANY PLAINS RESOURCES, INC.

WELL BELTZ 1

FIELD WILDCAT

COUNTY RENO STATE KANSAS

LOCATION NW-NE
 API SERIAL NO. 36 SEC. 25S TWP 5W RANGE 5W

Other Services:
 CNL-FDC-GR
 BHC-GR
 PML

Permanent Datum: GROUND LEVEL; Elev.: 1554
 Log Measured From KB 9 Ft. Above Perm. Datum
 Drilling Measured From KB

Elev.: K.B. 1563
 D.F. 1560
 G.L. 1554

Date	12-17-78					
Run No.	ONE					
Depth-Driller	4220					
Depth-Logger (Schl.)	4221					
Btm. Log Interval	4214					
Top Log Interval	262					
Casing-Driller	10 3/4 @ 263		@	@	@	@
Casing-Logger	262					
Bit Size	8 3/4					
Type Fluid in Hole	DRISPAC					
Dens.	Visc.	9.2	45			
pH	Fluid Loss	7.8	12.0ml	ml	ml	ml
Source of Sample	MUD PIT					
Rm @ Meas. Temp.	.405 @ 54 °F	.195 @ 112 °F	@	°F	@	°F
Rmf @ Meas. Temp.	.323 @ 52 °F	.149 @ 112 °F	@	°F	@	°F
Rmc @ Meas. Temp.	--- @ --- °F	--- @ --- °F	@	°F	@	°F
Source: Rmf Rmc	M --					
Rm @ BHT	.195 @ 112 °F	@	°F	@	°F	@
TIME	Circulation Stopped	12/17-0530				
	Logger on Bottom	12/17-0900				
	Max. Rec. Temp.	112	°F	°F	°F	°F
	Equip. Location	7749	WICH			
	Recorded By	JACKSON				
	Witnessed By Mr.	LUNA	JOHNSON			