


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Reno County, Sec. 14 Twp. 25S Rge. 11E 8 (W)
Location as "NE/CNW%SW%" or footage from lines C NE NE
Lease Owner Abercrombie Drilling, Inc.
Lease Name BEAUCHAMP Well No. 1
Office Address 801 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 12, 19 66
Application for plugging filed Verbally August 12, 19 66
Application for plugging approved Verbally August 12, 19 66
Plugging commenced August 12, 19 66
Plugging completed August 12, 19 66
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, verbally

Name of Conservation Agent who supervised plugging of this well Gilbert Toman, Holyrood, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4200 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	213	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud 4200' to 200'. First plug 200' to 125' with 25 sacks of cement. Filled hole from 125' to 30' with heavy mud. Second plug 30' to surface with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
AUG 18 1966
8-18-66
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.
Address 801 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jack K. Wharton (employee of owner) or (~~owner~~ ~~operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack K. Wharton
801 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 16th day of August, 19 66

My commission expires March 31, 1970.

Margo Dee Montgomery
Margo Dee Montgomery Notary Public.

CONTRACTOR'S WELL LOG

COMPANY: Abercrombie Drilling, Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 FARM: BEAUCHAMP #1
 LOCATION: C NE NE, Sec. 14-25S-8W
 Reno County, Kansas
 COMMENCED: August 1, 1966
 COMPLETED: August 12, 1966

0	40	Sand
40	90	Rock
90	225	Rock & Shale
225	1195	Shale
1195	1395	Lime & Shale
1395	1618	Shale & Lime
1618	1715	Lime
1715	3178	Shale & Lime
3178	3700	Lime
3700	3793	Shale & Lime
3793	3900	Chert
3900	3950	Lime & Shale
3950	4171	Shale & Lime
4171	4200	Simpson Sand
	4200	Rotary Total Depth

Set 8-5/8" surface casing at 213 feet with 185 sacks of cement.
 Dry and Abandoned.

ELECTRIC LOG TOPS:	ELEVATION:		
Heebner	2992	(-1407)	1585 K. B.
Lansing	3211	(-1626)	1584 D. F.
B/ Kansas City	3684	(-2094)	1578 G. L.
Mississippi	3799	(-2214)	
Kinderhook	3909	(-2324)	
Viola	4155	(-2570)	
Simpson	4161	(-2576)	
Rotary Total Depth	4200	(-2615)	

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 18 1966
 8-18-66


STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, Mildred Saxton, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 BEAUCHAMP, C NE NE of Section 14-25S-8W, Reno County, Kansas, as reflected by the files of Abercrombie Drilling, Inc.

Mildred Saxton
 Mildred Saxton, Secretary

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this sixteenth day of August, 1966.

Margo Dee Montgomery
 Margo Dee Montgomery, Notary Public



My commission expires March 31, 1970.