


15-155-20148-0000P

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD



Reno County, Sec. 1 Twp. 22S Rge. (E) 4 (W)
Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner Quintin Little
Lease Name Franz Well No. 1
Office Address P. O. Box 1509, Ardmore, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 29, 1970
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced March 29, 1970
Plugging completed March 29, 1970
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman of Holyrood
Producing formation Depth to top Bottom Total Depth of Well 3942 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	220'	13-3/8"	220'	None
	Casing		567'	8-5/8"	567	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 250 Feet,
Plug and 25 sax Cement; Mud to 40 Feet,
1/2 sax Halls, Plug Bridged w/Kelly;
10 sax Cement to Base of Cellar; 2 sax
Cement in Rat Hole. Job Completed
@ 12:30 P.M. on 3/29/70.

RECEIVED
STATE CORPORATION COMMISSION
APR 1 - 1970
CONSERVATION DIVISION
Wichita, Kansas


4-1-70

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sage Drilling Co., Inc.
Address 500 Bitting Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, SS.
Wayne W. Kahmeyer of Sage Drilling

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne W. Kahmeyer
500 Bitting Building, Wichita, Kansas
(Address)



Subscribed and Sworn to before me this 30th day of March, 1970

Louise K. Whitted - Notary Public.

My Commission Expires November 26, 1970.

DRILLERS LOG

FRANZ NO. 1

CASING RECORD: OPERATOR: Quintin Little DESCRIPTION:
 13-3/8" @ 222' w/200 sax cement CONTRACTOR: Sage Drilling Co., Inc. NW NW NW
 8-5/8" @ 567' w/300 sax cement COMMENCED: March 18, 1970 Sec. 1-22S-4W
 Reno Co., Kansas
 TOTAL DEPTH: 3942' COMPLETED: March 29, 1970 ELEVATION: 1459' KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Shale	0	70	
Shale & Sand	70	455	
Salt, Shale & Lime Shells	455	585	
Lime	585	1205	
Lime & Shale	1205	2165	
Lime	2165	2350	
Lime & Shale	2350	2470	
Lime	2470	2504	
Sand	2504	2540	
Lime & Shale	2540	2670	
Lime	2670	2999	
Lime & Shale	2999	3315	
Shale & Lime	3315	3413	
Lime	3413	3625	
Lime & Shale	3625	3740	
Lime	3740	3838	
Lime & Shale	3838	3849	
Sand, Lime & Shale	3849	3874	
Sand & Shale	3874	3905	
Lime	3905	3942	D&A

RECEIVED
 STATE CORPORATION COMMISSION
 APR 2 1970
 CONSERVATION DIVISION
 Wichita, Kansas
 4-2-70

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Wayne W. Kahmeyer
 Wayne W. Kahmeyer



Subscribed and sworn to before me this 30th day of March, 1970.

Louise K. Whitted
 Louise K. Whitted, Notary Public

My commission expires:
 November 26, 1970.