



15-079-30008-0000

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

May 22, 1965

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 26 1965  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Phillip Enders of German Drilling Co. has this  
date requested permission to plug the following described well:

Mr. Enders guarantees payment of the plugging fee.

Operator's full Name: G. D. & W. Oil Company

Complete Address: 502 Petroleum Bldg., Wichita, Kansas

Lease Name: Boyle Well No. 1

Location: NW NW NE Sec. 17 Twp. 24 Rge. 3 (X) (W) X

County Harvey Total Depth 3945' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole


Mr. Enders was instructed to plug the well as follows:

Fill hole with mud to 500'. Push plug and  $\frac{1}{4}$  sack hulls to  
500' and cement hole with 20 sacks through drill pipe.

Fill hole with mud to 200'. Push plug and  $\frac{1}{4}$  sack hulls to  
200' and cement hole with 20 sacks through drill pipe.

Fill hole with mud to 40'. Push plug and  $\frac{1}{2}$  sack hulls to

40' and cap hole with 10 sacks. Very truly yours,  
Bridge rathole, and cement with  
2 sacks.

  
Conservation Division Agent