



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 25 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Russell of Cities Service has this date requested permission to plug the following described well:

Mr. Russell guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: 3545 NW 58th St., Oklahoma City, Oklahoma

Lease Name: Tait "C" Well No. 5

Location: NW SE SE NW Sec. 27 Twp. 24 Rge. 33 XX (E) (W)

County: Finney Total Depth 5000' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Russell was instructed to plug the well as follows:

8 5/8" to 1952' circulated w/ cement. 4 1/2" to 4830' cemented.


Top perforations 4804' Plug bottom w/ 20 sacks cement.

Top of cement 4750' Mud 4750' to 520'

Spot 40 sacks cement 520' to 390' Mud 390' to 40'

Plug, Halls & 10 sacks cement 40' to 0'.

Very truly yours,


Conservation Division Agent