



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 28 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Makemson of Cities Service Oil has this
date requested permission to plug the following described well:

Mr. Makemson guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: Box 1098, Liberal, Kansas.

Lease Name: Tait "C" Well No. 4

Location: C SE NE 1/4 Sec. 27 Twp. 24 Rge. 33 (E) (W)

County: Finney Total Depth 5041' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Makemson was instructed to plug the well as follows:

8 5/8" to 1922' circulated w/ cement. 4 1/2" to 4920' cemented.


Top perforations 4784' Plug bottom w/ 25 sacks cement/

Top of cement 4430' Mud 4430' to 1270'

Spot 35 sacks cement 1270' to 1170' Mud 1170' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent