

State of Kansas



15-055-00829-0000 FORM - CP-2

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 27 1964
3-27-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Rose of Apache Corporation has this date requested permission to plug the following described well:

Mr. Rose guarantees payment of the plugging fee.

Operator's full Name: Apache Corporation

Complete Address: 823 South Detroit. Tulsa, Okla.

Lease Name: Westphal Well No. # 1

Location: C SE Sec. 26 Twp. 24 Rge. (E) (W) 31

County Finney Total Depth 2710' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Rose was instructed to plug the well as follows:

8 5/8"-341' Circulated w/cement. 4 1/2"-2708' cemented. Top Perf. 2694'

Plug bottom w/10 Sax. cement, top cement 2178'. Mud 2178' to 375'

Spotted 35 Sax. cement 375' to 265' Mud 265' to 45'

Plug, 15 Sax. cement 45' to 0

Very truly yours,


Conservation Division Agent