

State of Kansas



15-055-00817-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

RECEIVED
STATE CORPORATION COMMISSION

NOV 27 1974

CONSERVATION DIVISION
Wichita, Kansas

11-27-74

Plugging order were issued Nov 28-1973.

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Edgar Eves of Sargents Casing ^{pulling} has this date requested permission to plug the following described well:

Mr. Eves guarantees payment of the plugging fee.

Operator's full Name: Robert W. Lange

Complete Address: North Center, Garden City, Kan.

Lease Name: Catlett-Miller Well No. #1

Location: C. SE 1/4 Sec. 5 Twp. 24 Rge. (E)(W) 31

County: Finney Total Depth 2715 Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Eves was instructed to plug the well as follows:

324 ft of 7 7/8" surface casing. 2715
ft of 4 1/2" casing. Perforation 2678-2690
2 sacks of Cotton seed hull. + 15 Sacks of
Cement to seal perforations. 20 sacks
of Cement from 700-550 ft. 20 sacks
from 324 to 150 ft
10 Sacks Cement from
70 ft to 0.
1713 ft of 4 1/2" salvage

Very truly yours,
Charles J. Thomas
Conservation Division Agent