

State of Kansas



15-075-10121-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg.  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

OCT 7 10 56  
CONSERVATION DIVISION  
Wichita, Kans.

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Morton of Texaco Inc. has this

date requested permission to plug the following described well:

Mr. Morton guarantees payment of the plugging fee.

Operator's full Name: Texaco Inc.

Complete Address: 614 Bitting Building, Wichita, Kansas

Lease Name: K.A. Scott Well No. 1

Location: C SW SE Sec. 21 T. 24 R. 41 (E) (W)

County Hamilton Total Depth 2351' Oil Well

Gas Well X Input Well  SWD Well  D & A X Lost Hole

Mr. Morton was instructed to plug the well as follows:

7" to 409' circulated w/ cement. 4 1/2" to 2324' circulated w/ cement.

No Perforations Plug bottom w/ 15 sacks cement

Top of cement 2200' Mud 2200' to 459'

Spotted 10 sacks cement 459' to 359' Mud 359' to 50'

Plug, & 5 sacks cement 50' to 0'

Very truly yours,

Carl J. Eves  
Conservation Division Agent