



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

15-055-20008-0000

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Clift of Mallonee-Mahoney has this date requested permission to plug the following described well:

Mr. Clift guarantees payment of the plugging fee.

Operator's full Name: Mallonee-Mahoney Inc.

Complete Address: 925 Sutton Place, Wichita, Kansas

Lease Name: Sinn Well No. 1

Location: NW SE Sec. 17 Twp. 26 Rge. 33 (E) (W)

County: Finney Total Depth 5256' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Clift was instructed to plug the well as follows:

8 5/8" to 849' circulated w/ cement. 4 1/2" casing to 5256' cemented.

Top perforations 4980' Plug bottom w/ 20 sacks cement.

Top of cement 4500' Mud 4500' to 800'

Spot 40 sacks cement 800' to 700' Mud 700' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent