



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
JUL 8 1968
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-655-10127-0000

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

6-11-68

RECEIVED
STATE CORPORATION COMMISSION
JUL 11 1968
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Littrell of Mobil Oil Corp. has this

date requested permission to plug the following described well:

Mr. Littrell guarantees payment of the plugging fee.

Operator's full Name: Mobil Oil Corporation

Complete Address: Box 1934, Oklahoma City, Oklahoma

Lease Name: Stone "A" Well No. 2

Location: C NW NE Sec. 17 Twp. 26 Rge. 33 (E) (W)

County Finney Total Depth 5290' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Littrell was instructed to plug the well as follows:

8 5/8" to 1907' circulated w/ cement. 5 1/2" to 5202' cemented.

Top perforations 5020' Plug bottom w/ 25 sacks cement

Top of cement 4806' Mud 4806' to 1910'

Spotted 50 sacks cement 1910' to 1760' Mud 1760' to 0'

Weld Plate on 8 5/8" casing

Very truly yours,

Edgar J. Eves
Conservation Division Agent