

State of Kansas



15-155-20816-0000

FORM CP-2

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

## State Corporation Commission

### CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

September 2, 1981

#### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Kenneth Roach of Mustang Drlg. & Expl. has this  
date requested permission to plug the following described well:

Operator's Full Name: F & M Oil Company, Inc.

Complete Address: 422 Union Center, Wichita, Kansas 67202

Lease Name: Haines Well No. 1

Location: C SW SW Sec. 20 Twp. 25 Rge. 6 NE (W)

County: Reno Total Depth: 4060'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D&A X

Other well as hereafter indicated:       

Mr. Roach was instructed to plug the well as follows:

8-5/8"-367-275 sacks common. 2% gel 3% CC

Circulate hole and fill with mud. Pump 50 sacks cement through drill  
pipe at 375'. Fill hole with mud to 40'. Push plug and  $\frac{1}{2}$  sacks hulls  
to 40' and cap hole with 10 sacks cement. Cement rathole with 10 sacks  
cement.

Very truly yours,

  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION  
SEP - 9 1981  
CONSERVATION DIVISION  
Wichita, Kansas

9-9-81