



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

March 28, 1970

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 2 1970
CONSERVATION DIVISION
Wichita, Kansas

4-2-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Carl Nelson of Quinton Little has this
date requested permission to plug the following described well:

Mr. Nelson guarantees payment of the plugging fee.

Operator's full Name: Quinton Little

Complete Address: Box 1509, Ardmore, Oklahoma 73401

Lease Name: Franz Well No. 1

Location: NW NW NW Sec. 1 Twp. 22 Rge. 4 (E) (W) X

County: Reno Total Depth 3942' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Nelson was instructed to plug the well as follows:

Fill hole with mud to 250'. Push plug and 1/2 sack hulls to 250' and
cement hole with 25 sacks cement through drill pipe. Fill hole with
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10
sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,


Conservation Division Agent