

15-055-00860-0000

5-25

1 090001

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 2/26/52

App. NE NE SW, SEC. 29, T 24 S, R 32 W/E

2490 feet from S section line

2790 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4782

Lease Name Burnside "A" Well # 1

Operator: Ensign Operating Company

County Finney 86.97

Name & Address 621 17th Street, Suite 1800

Well Total Depth 2676 feet

Denver, CO 80293

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 10 3/4 feet 323

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Post & Mastin Well Service License Number 8438

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 30 1989

Address P.O. Box 297, Garden City, KS 67846

Company to plug at: Hour: 10 a.m. Day: 25 Month: 5 Year: 19 89

CONSERVATION DIVISION  
Kansas

Plugging proposal received from Leo Fife

(company name) Ensign Operating Company (phone) 303-293-9999

were: 7" at 2558' PBTD 2582' Open hole from 2558-2582'

1st plug circulate hole with 100 barrels water with 15 sx gel and 2 sx hulls,

2nd plug pump 50 sx cement to spot from 2400' back to 1900',

3rd plug pump 50 sx cement to spot from 1450' back to 950',

4th plug pump 35 sx cement to spot from 335' back to 3'.

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:50 p.m. Day: 25 Month: 5 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug ran 100 barrels water with 15 sx gel and 2 sx hulls,

2nd plug pumped 50 sx cement from 2400-1900',

3rd plug pumped 50 sx cement from 1450-950',

4th plug pumped 35 sx cement from 335-3'.

Tried to pump between 10 3/4" & 7" annulus but was full and pipe ruptured at surface.

Richard Lacey also witnessed.

Remarks: Used 60/40 Pozmix 2% gel by Halliburton. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-2-89

INV. NO. 24950

5-25

Signed Michael B Wilson  
(TECHNICIAN)