

1050362

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-055-20,316-0000  
C SW SW NE, SEC. 35, T 24 S, R 31 W/E  
2970 feet from NXX SE Corner of section line  
2310 feet from WXX SE Corner of section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5639

Lease Name Tate Well # 1

Operator: Energy Exploration & Production, Inc  
Name & Address: 5501 Fox Ridge Drive  
Mission, KS 66222

County Finney

Well Total Depth 2750 89.38 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 610

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Post & Mastin Well Service, Inc. License Number 8438

Address P. O. Box 297, Garden City, KS 67846

Company to plug at: Hour: 11:00 am Day: 12 Month: October Year: 19 84

Plugging proposal received from Clay Hendricks

(company name) Energy Exploration & Production (phone) 913-722-5955

were: 4 1/2" set at 2750' Perfs at 2670-80

1st plug pump 50 sx cement to bottom

2nd plug at 1400' with 50 sx cement

3rd plug at 700' with 130 sx cement

Pump 30 sx in 8 5/8" annulas

Plugging Proposal Received by Richard M. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 6:02 pm Day: 12 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 2750' Perfs at 2670-80'

1st plug pumped 50 sx cement to bottom, 2nd plug at 1400' with 50 sx cement, 3rd plug at 700' with 130 sx cement, and pumped 30 sx cement in 8 5/8" annulas

10-17-84  
STATE CORPORATION COMMISSION

OCT 17 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Richard M. Lacey  
(TECHNICIAN)

DATE 10-18-84

INV. NO. 4391