

1 051599

11-17

API NUMBER 15-055-20,269-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C W/2, SEC. 3, T 24 S, R 31 W/R  
2640 feet from S section line  
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4058

Lease Name Fuller Well # 1-3

Operator: American Warrior, Inc.

County Finney

Name & Address P.O. Box 399

Well Total Depth 2740 89.05 feet

Garden City, KS 67846

Conductor Pipe: Size feet

Surface Casing: Size 7" feet 348

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address Ness City, KS

Company to plug at: Hour: 1 p.m. Day: 17 Month: 11 Year: 19 92

Plugging proposal received from Kevin Wiles

(company name) American Warrior (phone) 316-275-2963

were: 4 1/2" at 2694' w/100 sx cement, PBDT 2684', Perfs at 2677-82'

1st plug run tubing to 2670' and pump 1 sx hulls and 35 sx cement,

2nd plug pull tubing to 2000' and circulate cement to surface with 155 sx,

3rd plug pump 210. sx cement down 7" X 4 1/2" annulus.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 5:30 p.m. Day: 17 Month: 11 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug ran tubing to 2670' and pumped 1 sx hulls and 35 sx cement,

2nd plug pulled tubing to 2000' and circulated cement to surface with 155 sx cement,

3rd plug pumped 210 sx cement down 7" X 4 1/2" annulus.

Maximum pressure 200 psi and shut in 200 psi.

RECEIVED

NOV 20 1992

Remarks: Used 60/40 Pozmix 3% gel 2% cc by Halliburton. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED

I (did / did not) observe this plugging.

DATE 12-8-92

INV. NO. 37018

Signed Richard M. Lacey (TECHNICIAN)

