

1 010187

DEC 4 1986

API NUMBER 15-097-20,971-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION C S/2 S/2 S/2 SEC. 36, T 27 S, R 16 W/E  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

330 feet from S section line  
2640 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5255

Lease Name John Perdue Well # 1

Operator: McGinness Oil Company  
Name & Address: 1026 Union Center Bldg.,  
Wichita, KS 67202

County: Kiowa 154.38

Well Total Depth 4750 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 427

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 10 a.m. Day: 4 Month: 12 Year: 19 86

Plugging proposal received from John Luther

(company name) Pratt Well Service (phone) 316-672-2531

were: 5 1/2" at 4749' Elevation 2091' GL

1st plug sand back to 4505' and dump 5 sx cement on top of sand through bailer,

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,  
release plug and pump 125 sx cement.

Plugging Proposal Received by Jack Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11 a.m. Day: 4 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4505' and dumped 5 sx cement on top of sand through bailer,

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,  
released 8 5/8" wiper plug and pumped 125 sx cement.

DEC 9 1986 12-9-86

Maximum pressure 800 psi and shut in 500 psi.

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2330' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I (do not) observe this plugging.

Signed  (TECHNICIAN)

DATE 12-10-86

WIV. NO. 15575