

1 090019  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

10-17  
API NUMBER 15- 097-21,226-0000  
SE SW SE, SEC. 36, T 27 S, R 16 W/E  
330 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3532

Lease Name Swafford Well # 1-36

Operator: CMX Inc.  
Name & Address: 1026 Union Center  
Wichita, KS 67202

County Kiowa 153.56

Well Total Depth 4725 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 405

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 11:45 a.m. Day: 17 Month: 10 Year: 19 90

Plugging proposal received from Jeff Clarke

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4724', PBD 4696', Perfs at 4643-48'

1st plug sand back to 4590' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:20 p.m. Day: 17 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4590' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 650 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2300' well casing. (if additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

DATE 10-26-90

INV. NO. 29749

Signed [Signature] (TECHNICIAN)