

1 010186

DEC 4 1986

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-21,046-0000
SE SW SW, SEC. 36, T 27 S, R 16 W/E
330 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5255

Lease Name Don Peterson Well # 1
County Kiowa 154.38

Operator: McGinness Oil Company
Name & Address 1026 Union Center Bldg.
Wichita, KS 67202

Well Total Depth 4750 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 429

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 11:45 a.m. Day: 4 Month: 12 Year: 1986

Plugging proposal received from John Luther

(company name) Pratt Well Service (phone) 316-672-2531

were: PBD 4668' Perfs at 4650-4702' 5 1/2" at 4748' Elevation 2105' GL

1st plug sand back to 4462' and dump 5 sx cement on top of sand through bailer,
2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,
release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Jack Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15 p.m. Day: 4 Month: 12 Year: 1986

ACTUAL PLUGGING REPORT 1st plug sanded back to 4462' and dumped 5 sx cement on top of
sand through bailer.

2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,
released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 600 psi and shut in 200 psi.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 2343' of 5 1/2" casing. Used 60/40 Pozmix 6% gel by B.J. Titan.

(If additional description is necessary, use BACK of this form.)

INVOICED
XXXXXXXX observe this plugging.

DEC 9 1986

CONSERVATION DIVISION
Wichita, Kansas

DATE 12-10-86

Signed Jack Luthi
(TECHNICIAN)

INV. NO. 15578