

1 010250

6-8-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

55, API NUMBER 15-151-21,374-0000
NW OF C
N/2 NW, SEC. 14, T 27 S, R 12 W/E
4645 feet from S section line
3990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Barnes "B" Well # 1-14

Operator: Texas Energies, Inc.
Name & Address P.O. Box 947
Pratt, KS 67124

County Pratt 149.50
Well Total Depth 4600 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 303

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2:50 p.m. Day: 8 Month: 6 Year: 19 87

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4530' PBSD 4488' Perfs at 3954-56, 3866-68'

1st plug Bridge at 1400' - Allied pumped water and wiper plug to 3790' and pressure up to 500 #.
sand back to 3810' and dump 4 sx cement on top of sand through bailer,

2nd plug dump 8 sx cement on top of wiper plug at 3790' with bailer,

3rd plug pump 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 130 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30 p.m. Day: 8 Month: 6 Year: 1987

ACTUAL PLUGGING REPORT 1st plug sanded back to 3810' and dumped 4 sx cement on top of sand
through bailer,

2nd plug pumped 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, 130 sx cement.

Maximum pressure 600 psi and shut in 200 psi.

NOTE: On 6/1/87 ran wiper plug to 3790' with 500 lbs. pressure, ran 8 sx cement with bailer.

Jack Luthi witnessed.

STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2621' of 4 1/2" casing. JUN 19 1987
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

(If desired, observer observe this plugging.)

Signed Jack Luthi
(TECHNICIAN)

INVOICED
DATE 6-22-87
INV. NO. 17297