

1060327

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-055-20,565-0000

C NW SW, SEC. 17, T 26 S, R 33 W/X

1980 feet from N SE Corner of XX section line

4470 feet from W SE Corner of XX section line

STONE FARM

TECHNICIAN'S PLUGGING REPORT

Operator License # 7771

Lease Name UNIT Well # 1

Operator: Pan Western Energy Corporation
Name & Address 324 South Main Street, Suite 711
Tulsa, OK 74103

County Finney

Well Total Depth 5258 170.89 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1552

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Slawson Drilling Company, Inc. License Number 5657

Address 200 Douglas Building Broadway & Douglas, Wichita, KS 67202

Company to plug at: Hour: 3:00 am Day: 7 Month: September Year: 19 84

Plugging proposal received from Wayne Frederick

(company name) Slawson (phone) 316-263-3201

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1820' with 70 sx cement

2nd plug at 1110' with 40 sx cement

3rd plug at 620' with 30 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:00 am Day: 7 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1820' with 70 sx cement, 2nd plug at 1110' with

40 sx cement, 3rd plug at 620' with 30 sx cement, 4th & 5th plugs - solid bridge - hulls

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement.

STATE CORPORATION COMMISSION

9-17-84
SEP 17 1984

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% CC by Halliburton

(If additional description is necessary, use BACK of this form.)

(check) did not observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

INVOICED
DATE 9-26-84

WV. NO. 3858 9-7