

7-25

2-030583

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER: 155-20,874-0000
C SW SE, SECTION 11 TOWNSHIP 25 RANGE 6W

OPERATOR LICENSE # 5471 660 FEET FROM S SECTION LINE
1980 FEET FROM E SECTION LINE

OPERATOR Aurora, Inc.
NAME & P. O. Box 12747
ADDRESS Wichita, KS 67277

LEASE NAME: Everett #1
COUNTY: Reno
WELL TOTAL DEPTH: 3707' -120.48

PIPE: _____
SURFACE CASING: 8-5/8" @ 286'w/200 sx

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SLD _____ D&A _____
OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Kelso Casing Pulling
ADDRESS: Chase, KS LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 9:30 DAY: 25 MONTH: 7 YR: 1990
PLUGGING PROPOSAL RECEIVED FROM: Bill Shingle
COMPANY NAME: Kelso Casing Pulling PHONE: 316-938-2943

WERE: 4-1/2" @ 3650' w/250 sx - tubing cemented in hole at
1328' - recover avail pipe - circ 35 sx thru 4-1/2"
casing @ 1000' - pull pipe to 350' - circ cmt to surf -
pull pipe - fill hole to surface.

PLUGGING PROPOSAL RECEIVED BY: John Sanders

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (_____) NONE (_____)

COMPLETED: HOUR: 17:00 DAY: 25 MONTH: 7 YEAR: 1990

ACTUAL PLUGGING REPORT:
Perfs @ 3520-30' - squeezed w/cmt - TOC 3500' - tried
drlg out w/tubing - twisted off @ 1328' - unable to
fish - shot pipe @ 1300' - pulled to 975' - circ 35 sx
60/40 4% gel - pulled pipe to 365' - circ cmt to surf -
pulled pipe out of hole & refilled to surface.

REMARKS: Allied Cmt #6255 150 sx 60/40 4% gel

I DID OBSERVE THIS PLUGGING. STATE CORPORATION COMMISSION

INVOICED

AUG 15 1990

8-15-90

DATE: 8-17-90

INV. NO. 28997

CONSERVATION DIVISION
Wichita, Kansas

Merlan Unruh
Merlan Unruh (AGENT)