

Called 8/21/84 waiting on a memo to help fill out form.

2 050144

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-155-20,983-0000

Su/4, SEC. 12, T. 25 S., R. 6 W.

1500 feet from ~~NS~~ section line

450 feet from ~~NE~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7629

Lease Name Schrag Well # 1

Operator: Lone Star Oil Inc.

County Beno

Name & Address Box 1702

Well Total Depth 4025 ^{130.81} feet

^{316'}
^{1663'}
^{4093'}
Hutchinson, KS.

Conductor Pipe: Size - feet -

67504

Surface Casing: Size 8 9/8 feet 165

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Allen Dvlg. Co. License Number 5418

Address Great Bend, KS.

Company to plug at: Hour: 1:00 Day: 16 Month: 6 Year: 19 84

Plugging proposal received from Jim Ehrlich

(company name) Allen Dvlg. (phone) _____

were: 35 SX. @ 4000

RECEIVED STATE CORPORATION COMMISSION 35 SX. @ 1250

JUN 27 1984 35 SX. @ 200

CONSERVATION DIVISION 20 SX. @ 40
Wichita, Kansas

10 SX. in Rat
10-27-84 Plugging Proposal Received by Glenn Ward
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:00 PM Day: 16 Month: 6 Year: 19 84

ACTUAL PLUGGING REPORT Fill hole with mud. Run Drill Pipe
To 4000 ft. & spot 35 SX. Cement, Disp. with mud
Pull Drill Pipe to 1250 & spot 35 SX. Cement there
Disp. with mud. Pull Drill Pipe to 200 ft. & spot
35 SX. Cement, Disp. with water. Pull Drill Pipe.
Push Plug to 40 ft. & fill hole with Cement.

Remarks: _____

(If additional description is necessary, use BACK of this form.)

INVOICED

I (did / did not) observe this plugging.

DATE 7-3-84

Signed Glenn Ward
(TECHNICIAN)

INV. NO. 2243

10-16 JUL 17 1984 AUG 3 1984

OCT 23 1984
Jim Letter

FORM CP-2/3
Rev. 01-84