

15-185-20539-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 33 Twp. 25S Rge. (E) 14 (W)
Location as "NE/CNW*SW*" or footage from lines C SW SE
Lease Owner O. A. Sutton
Lease Name Gereke Well No. 1
Office Address 800 Sutton Place, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 23 19 75
Application for plugging filed June 23 19 75
Application for plugging approved June 23 19 75
Plugging commenced June 23 19 75
Plugging completed June 23 19 75
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation Depth to top Bottom Total Depth of Well 4535 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	413'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug #1 @ 360' with 35 sacks cement. Plug #2 @ 40' with 15 sacks cement. Two sacks in rathole. Job by Sun Job complete at 12:45 p.m. 6-23-75.

RECEIVED
STATE CORPORATION COMMISSION

JUL 14 1975

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.
Address 800 Sutton Place, Wichita, Kansas 67202


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jack G. Paulsen (employee of owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack G. Paulsen
800 Sutton Place, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of July 1975.

My commission expires June 28, 1978. Jean S. Taylor Notary Public.



15-185-20539-0000

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

Gereke #1
C-SW-SE Sec 33-25S-14W
Stafford County Kansas

Commenced: 6-11-75

Completed: 6-23-75

OPERATOR: O. A. SUTTON

Depth From	to	Formation	Remarks
0	20	Sand	Ran 10 jts of used 8 5/8" csg
20	230	Soil-Sand	set @ 413' Cemented w/363 sks
230	420	Sand-Shale	Common 3% CC
420	920	Shale-Redbed	P.D. @ 11:00 p.m. 6-11-75
920	937	Anhy	Ran 2" to 25' Cemented w/
937	1060	Shale	35 sks Common 3% CC
1060	1700	Shale-Shells	Job Complete @ 1:45 a.m. 6-12-75
1700	1945	Lime-Shale	
1945	2075	Lime	
2075	2330	Lime-Shale	
2330	2770	Lime	
2770	3210	Lime-Shale	
3210	3390	Lime	
3390	3570	Lime-Shale	
3570	4535	Lime	
	4535 TD		DRY & ABANDONED

I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled C-SW-SE Sec 33-25S-14W, Stafford County Kansas to the best of my knowledge and belief.

James S. Sutton II
JAMES S. SUTTON II

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State on this 8th day of July, 1975, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

Elizabeth J. Edwards
ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission Expires: February 6, 1979.

RECEIVED
STATE CORPORATION COMMISSION

JUL 14 1975

CONSERVATION DIVISION
Wichita, Kansas

