

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Reno County. Sec. 34 Twp. 25 S Rge. 4 (E) (W)

Location as "NE/CNW/SW" or footage from lines. C SW SW NW

Lease Owner Phillips Petroleum Company

Lease Name Manning Well No. 1

Office Address Box 779 - Great Bend, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 8/19/43 19.

Application for plugging filed 6/16/58 19.

Application for plugging approved 6/17/58 19.

Plugging commenced 6/28/58 19.

Plugging completed 7/2/58 19.

Reason for abandonment of well or producing formation Uneconomical to operate

If a producing well is abandoned, date of last production 6/18/58 19.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Fred Hampel

Producing formation Viola Depth to top 4099 Bottom Total Depth of Well 4102 1/2 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
LKC	Dry	2855		8 5/8"	297	None
Misner Sand	Dry	4084		5 1/2"	4099	3208
Viola	Oil	4099				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Dumped sand 4102 1/2' to 4075'. Dumped 5 sx. cement to 4040'. Mudded hole to 250'.  
Set rock bridge to 240', 20 sx. cement to 180', mudd to 40', rock bridge to 30',  
10 sx. cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
7-7-58  
JUL 7 1958

Name of Plugging Contractor West Supply  
Address Chase, Kansas.

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
A. J. Willis

(employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Willis

Box 779 - Great Bend, Kansas.

(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of July, 19 58

My commission expires 11/18/61

Joseph P. Muehl  
Notary Public.

PLUGGING  
FILE SEC 34 T 25 R 4W  
BOOK PAGE 108 LINE 17

EXPLORATION RECORD

Lease Manning

Well 1

Formation Name	Top	Base	Remarks
Sand and red bed	0	129	
Red bed and red rock	129	301	
Red bed	301	339	
Shale	339	599	
Shale and Lime	599	759	
Shale	759	904	
Shale and salt	904	1009	
Shale and shells	1009	1236	
Sandry lime	1236	1344	
Shale	1344	1594	
Shale and shells	1594	1724	
Shale	1724	2299	
Lime	2299	2471	
Lime and Shale	2471	2609	
Lime	2609	2727	
Lime and Shale	2727	2875	Top LKC 2855
Lime	2875	3109	
Shale	3109	3179	
Lime	3179	3206	
Shale	3206	3219	
Lime and shale	3219	3355	
Shale	3355	3412	
Lime and shale	3412	3465	
Shale	3466	3638	
Lime and Shale	3638	3669	
Chat	3669	3716	
Chat and shale	3716	3749	
Chat	3749	3887	
Shale	3887	3909	
Chat and lime	3909	3932	
Chert	3932	3962	
Shale and chert	3962	3989	
Shale	3989	4099	Top Misner Sand 4084
Lime	4099	4102 $\frac{1}{2}$	Top Viola 4099

7-7-58  
JUL

CONSERVATION I  
Wichita, Kan

**PLUGGING**  
FILE SEC 34 T. 25 R 4W  
BOOK PAGE 108 LINE 17