


15-155-02711-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Reno County. Sec. 34 Twp. 25S Rge. 4 (W)
Location as "NE/CNW'SW" or footage from lines 990' fr. W & 990' fr. S, NW/4
Lease Owner Phillips Petroleum Company
Lease Name Manning Well No. 3
Office Address Box 779, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 17, 19 50
Application for plugging filed September 5, 19 57
Application for plugging approved September 9, 19 57
Plugging commenced September 19, 19 57
Plugging completed September 23, 19 57
Reason for abandonment of well or producing formation Uneconomical to operate.

If a producing well is abandoned, date of last production August 12, 19 57
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Ruel Durkee
Producing formation Viola Depth to top 4103 Bottom NR Total Depth of Well 4106 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner	Dry	2634	NR	8-5/8"	345.51'	None
Toronto	Dry	2651	NR	5-1/2"	4096.00'	2832'
Brown Lime	Dry	2826	NR			
LKC	Dry	2860	NR			
Viola	Oil	4103	4106			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Filled with sand 4106' to 3990'. Dumped 6 sx. cement 3990' to 3948'. Mudded hole from 3948' to 310'. Rock bridge 310' to 300'. 15 sx. cement 300' to 255'. Mud 255' to 25'. Rock bridge 25' to 15'. 5 sx. cement to base of cellar. Well plugged and abandoned 4:00 P.M. 9-23-57.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
A. J. Willis (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) A. J. Willis
Box 779, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 26th day of September, 19 57
My commission expires 11-18-57
Joseph H. Beal Notary Public.

RECORDED
STATE CORPORATION
9-27-57
SEP 27 1957
PLUGGING
CONSERVATION DIVISION FILE SEC 34 TWP 25S R 4W
Wichita, Kansas BOOK PAGE 43 LINE 4

Phillips Petroleum Company EXPLORATION RECORD
 Manning No. 3 - 990' from West and 990' from South lines, NW/4 Sec. 34-25S-4W, Reno
 County, Kansas.

Lease Manning

Well 3

Formation Name	Top	Base	Remarks
Surface Clay, shale, shells	0	360	
Shale and shells	360	475	
Anhydrite	475	485	
Shale, shells, salt	485	615	
Shale and shells	615	915	
Shale and lime	915	1280	
Lime	1280	1525	
Broken Lime	1525	1630	
Shale	1630	1685	
Shale and shells	1685	1925	
Lime and shale	1925	2380	
Lime	2380	2480	
Lime and shale	2480	2900	
Lime	2900	3485	
Lime and shale	3485	3595	
Sandy Shale	3595	3645	
Shale	3645	3648	
Chat - Chert	3648	3735	
Lime	3735	3978	
Shale	3978	4085	
Shale and sand	4085	4095	
Shale	4095	4105	
Lime	4105	4106	

FORMATION TOPS:

Heebner	2634
Toronto	2651
Brown Lime	2826
LKC	2860
Viola	4103

PLUGGING
 FILE SEC 34 T 25 R 4W
 BOOK PAGE 43 LINE 4

RECEIVED
 DIVISION
 9-27-57
 DIVISION
 IS