

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Reno SEC. 34 TWP. 25 RGE. 4w E/W
Location as in quarters or footage from lines:
W/2 SW NW

Locate Well
correctly on above
Section Platt.

Lease Owner Africo Explorations Inc, Ltd
Lease Name Lyle Newby #1 Well No. _____
Office Address 2225 East 21st ST., Suite 205, Wichita, Ks. 67214
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 8/8/83
Plugging completed 8/10/83
Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren Kirkpatrick
Producing formation _____ Depth to top _____ bottom _____ T.D. 4105'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	267'	none
				5 1/2"	4104.5'	3246'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Ran sand to 4050' & set 5 sacks cement. Shot pipe at 3277'. Pulled total
of 79 joints. Plugged well with 6 hulls, 10 gel, & 125 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1983

Plugging complete

CONSERVATION DIVISION
Wichita, Kansas

8-15-83

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of August, 19 83

My Commission expires:



Irene Hoover
Notary Public.

DONALD J. MELLAND * PETROLEUM GEOLOGIST

401 Peoples Bank Building * Post Office Box 783 * McPherson, Kansas 67460
Office (316) 241-7907 * Residence (316) 241-4582

G E O L O G I C A L R E P O R T

Africo Explorations Inc., LTD
Newby # 1
W/2 SW NW, Sec. 34-25-4W
Field: Hilger
Reno County, Kansas

November 20, 1982
Elevation: 1563 KB
Comm: 11/6/82; Comp: 11/10/82
Casing: 8-5/8" @ 267'/200sx.
5-1/2" @ 4104.5'/75sx.

FORMATION TOPS

Brown Lime	2831 (-1268)
Lansing	2868 (-1305)
Mississippian	3653 (-2090)
Mississippian-Osage	3678 (-2115)
Kinderhook	3981 (-2418)
Misener Sand	4087 (-2524)
Viola	4104 (-2541)
RTD	4105 (-2542)

Cores: None

Drill Stem Tests: None

Electrical Logs: None

Gas Detector: Was furnished by Davis Mud & Chemical, Inc. No gas kicks were noted throughout the drilling of the well.

Measurements: Were taken from kelly bushing, 5 feet above ground level. Drill pipe was strapped at 3966 feet - no corrections were made.

FORMATION SUMMARY

LANSING

2893-2898 Limestone: buff to tan, finely crystalline, oolitic, oolitic, poor porosity, no shows of oil.

3270-3274 Limestone: buff to tan, coarse oolitic, oolitic in part, poor porosity, no shows of oil.

MISSISSIPPIAN

8

3662-3670 Chert: white, slightly greenish in part, sharp, small amount of leached with poor porosity, no shows of oil or gas.

MISSISSIPPIAN-OSAGE

3678-3715 Chert: white, leached, tripolitic, poor and fair porosity, no shows of oil or gas.


MISENER SAND

4087-4090 Sandstone: clear and brownish, medium to coarse grained, pyritic, poor porosity, no shows of oil or gas.

VIOLA

4104-4105 Dolomite: white and gray, mottled, coarsely crystalline, poor and fair porosity, show of oil, slight show of gas, strong odor. This zone should be tested.

Respectfully submitted,



Donald J. Melland

DJM/f

DRILLING TIME

Africo Explorations Inc., LTD
Newby # 1

Sec. 34-25-4W
W/2 SW NW

Elevation: 1563 KB
Reno County, Kansas

Depth	Time					Remarks					
2800-2810	2	1	1	2	2	1	2	1	2	1	
20	2	1	2	1	1	1	2	1	1	2	
30	1	2	1	1	1	2	1	2	1	1	
40	2	2	3	5	5	4	3	2	2	2	
50	2	2	2	2	3	2	2	2	2	2	
60	2	3	2	2	2	2	2	2	2	2	
70	2	2	3	4	3	3	2	2	3	5	
80	6	4	4	5	4	4	3	4	3	5	
90	4	3	3	4	3	4	4	3	4	3	
2890-2900	2	3	4	1	1	1/2	1/2	1	3	3	Trip @ 2893'
10	4	4	4	4	5	3	4	3	4	3	
20	3	3	3	4	3	5	5	5	5	3	
30	4	5	4	5	5	4	2	3	3	3	
40	4	2	3	3	2	3	2	3	3	4	
50	4	4	4	4	4	4	3	4	3	5	
60	3	3	3	3	4	4	4	5	4	4	
70	5	4	4	4	4	4	4	3	3	4	
80	4	5	4	4	4	4	2	3	2	3	
90	2	2	3	2	3	3	4	5	3	3	
2990-3000	3	2	3	2	3	4	3	3	2	3	
10	2	5	4	3	4	4	3	3	3	1	
20	3	3	2	3	2	4	1	3	2	2	
30	3	2	5	3	5	3	3	3	3	3	
40	3	2	3	3	2	2	3	2	2	2	
50	3	1	2	3	3	3	3	5	3	5	
60	5	5	5	3	5	5	6	6	5	5	
70	4	3	4	2	2	1	1	2	3	4	
80	2	3	2	1	2	2	3	2	3	3	
90	3	2	2	3	3	2	4	3	2	3	
3090-3100	4	2	2	2	4	2	2	3	3	3	
10	2	3	3	3	3	3	4	3	4	3	
20	3	3	4	4	5	5	5	4	5	5	
30	5	4	4	5	4	4	4	4	4	4	
40	5	7	6	5	6	5	4	5	3	6	
50	7	4	4	3	5	5	6	6	5	5	
60	5	6	5	5	5	5	4	5	5	4	
70	5	7	4	4	4	4	3	4	4	5	
80	3	2	3	5	4	3	4	4	6	7	
90	6	7	6	5	7	7	7	7	7	6	
3190-3200	6	6	7	6	6	6	6	5	6	6	

Depth	Time					Remarks					
3200-3210	7	6	7	5	7	4	4	6	6	5	
20	6	4	4	2	4	5	6	6	7	6	
30	6	5	4	4	4	4	4	3	4	2	
40	4	5	6	6	6	7	7	8	6	7	
50	7	7	7	7	8	7	7	7	8	7	
60	7	6	7	7	6	6	5	7	5	7	
70	6	6	5	7	6	4	3	5	7	5	
80	3	1	2	4	5	6	7	6	7	6	
90	7	7	7	6	4	9	6	8	8	10	
3290-3300	4	2	7	7	8	8	8	6	5	3	
10	5	5	6	6	5	5	3	7	8	9	
20	8	6	7	6	7	11	10	9	7	5	Trip @ 3317'
30	5	8	6	8	7	6	6	6	5	7	
40	7	9	7	5	9	6	5	6	7	5	
50	6	6	6	6	7	4	6	5	6	6	
60	7	8	7	6	6	5	4	3	4	3	
70	2	2	2	3	4	6	4	6	5	6	
80	5	6	6	7	7	7	7	7	6	7	
90	5	5	3	4	4	5	4	4	6	7	
3390-3400	6	7	8	6	8	7	4	2	3	5	
10	5	6	7	7	3	4	5	5	5	6	
20	6	7	7	6	6	6	6	6	6	6	
30	6	7	6	6	6	6	6	6	6	6	
40	7	6	7	6	7	5	6	6	6	6	
50	5	5	3	2	2	3	5	5	6	5	
60	6	6	7	6	7	6	6	7	7	8	
70	8	7	9	7	7	9	8	9	8	9	
80	7	6	6	6	6	4	3	7	7	7	
90	6	3	4	4	8	7	7	9	8	7	
3490-3500	9	8	8	9	8	8	7	6	4	5	
10	2	6	8	6	8	8	7	7	8	9	Trip @ 3503'
20	9	8	5	5	4	5	5	5	5	4	
30	5	9	8	8	8	7	6	7	6	6	
40	6	6	4	5	6	6	7	4	4	3	
50	2	2	2	2	2	2	2	3	3	3	
60	4	6	4	4	3	3	3	5	7	4	
70	4	3	2	2	2	2	3	3	3	2	
80	4	4	2	3	2	4	5	5	7	6	
90	4	3	5	5	3	7	4	4	4	4	
3590-3600	4	4	4	2	2	2	2	4	5	4	

Newby # 1

Drilling Time

Page 3

Depth	Time					Remarks					
3600-3610	4	6	5	5	4	2	2	2	1	1	
20	2	2	2	4	5	2	2	2	3	4	
30	2	2	2	3	2	2	3	3	3	2	
40	3	2	3	4	2	3	4	4	4	3	
50	4	4	4	4	5	5	6	5	5	5	
60	4	5	5	8	6	6	6	7	5	5	
70	6	5	3	2	3	2	2	2	2	3	Circ. @ 3670'
80	5	6	4	5	6	7	5	2	4	4	
90	4	4	3	2	2	1	2	2	2	2	
3690-3700	1	2	1	2	1	1	1	2	1	1	Circ. @ 3700'
10	2	1	1	1	1	2	2	1	1	2	
20	1	1	2	2	3	4	5	1	2	4	
30	2	3	2	2	4	2	5	6	7	8	
40	8	7	6	9	4	7	7	7	6	7	
50	6	7	7	7	6	7	7	5	5	4	
60	3	4	4	6	8	9	7	6	8	7	
70	9	8	8	7	9	9	9	9	9	6	
80	7	9	9	8	8	8	8	8	7	8	
90	7	7	6	5	7	7	5	7	6	6	
3790-3800	8	7	6	7	8	7	7	8	7	9	Trip @ 3802'
10	8	6	5	6	6	7	7	7	7	6	
20	6	6	6	6	5	6	6	7	6	7	
30	6	7	5	6	6	5	5	6	4	4	
40	5	4	5	5	5	7	6	6	5	7	
50	6	6	6	3	3	3	4	3	4	5	
60	7	6	7	8	7	8	6	7	8	7	
70	6	8	6	6	7	6	5	6	7	6	
80	6	7	7	6	5	6	7	6	7	8	
90	7	7	5	8	7	8	8	6	7	8	
3890-3900	7	7	7	8	9	10	8	9	9	11	
10	7	10	9	9	8	8	9	9	8	9	
20	7	7	9	8	9	8	9	9	9	9	
30	8	8	8	9	9	10	9	9	9	10	
40	8	9	7	8	7	8	8	5	7	7	
50	8	8	7	6	8	7	7	7	7	8	
60	8	7	6	5	8	7	7	8	7	6	
70	7	9	9	9	10	11	6	9	9	8	Trip @ 3966'
80	9	10	5	5	5	9	10	9	10	9	
90	5	8	9	8	8	8	9	9	9	9	
3990-4000	8	8	9	9	8	7	7	6	6	5	

Newby # 1

Drilling Time

Page 4

Depth	Time					Time					Remarks
4000-4010	6	6	6	6	6	5	6	6	5	6	
20	5	5	6	5	6	6	6	6	6	5	
30	6	5	5	7	6	5	6	6	6	5	
40	5	5	6	5	7	6	7	6	7	6	
50	6	7	6	6	7	6	8	6	6	6	
60	6	7	5	7	5	6	7	6	9	5	
70	7	7	6	6	7	6	6	7	6	7	
80	5	7	6	6	7	6	5	7	5	7	
90	5	6	6	6	5	6	5	7	7	8	
4090-4100	8	8	6	7	8	9	10	8	8	9	Circ. @ 4092', 4096', & 4100'
4100-4105	10	10	7	7	6						Circ. @ 4103' & 4105'