

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-155-20, 873-0000

LEASE NAME Fry

WELL NUMBER 1

4620 Ft. from (S) Section Line

3300 Ft. from (E) Section Line

SEC. 2 TWP. 25 RGE. 5 (E) or (W)

COUNTY Reno

Date Well Completed 6-7-82

Plugging Commenced 10-18-96

Plugging Completed 8-28-97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Gressel Oil Field Service, Inc.

ADDRESS Box 438, Haysville, KS 67060

PHONE# (316) 524-1225 OPERATORS LICENSE NO. 3004

Character of Well gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-16-96 (date)

by Jack Luthy (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Indian Cave Depth to Top 1556' Bottom 1558 T.O. 1624

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content surface	From surf	To	Size	Put in	Pulled out
		surf	286	8 5/8	286	0
	production	surf	1624	4 1/2	1624	40'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set
see attached

Name of Plugging Contractor Gressel Oil Field Service, Inc. License No. 3004

Address Box 438, Haysville, KS 67060

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gressel Oil Field Service, Inc. (has been paid)

STATE OF Kansas COUNTY OF Sedgwick, ss.

R. A. Schrenner (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) R. A. Schrenner
Box 438, Haysville, KS 67060

SUBSCRIBED AND SWORN TO before me this 3rd day of September, 19 97

DEBRA K. HILL JOHNSON
MY APPL. EXP. APRIL 15, 1999

[Signature]
Notary Public

My Commission Expires: April 15, 1999

DEBRA K. HILL JOHNSON
STATE OF KANSAS
MY APPL. EXP. APRIL 15, 1999

FRY #1
PLUGGING REPORT

- 10-28-96 Set CIBP at 1500'. Dump bailed one sack cement on plug. Worked pipe and shot off at 800'. Shut well in overnight.
- 10-29-96 Pulled casing to 750' FS. Started pumping down casing to get circulation. Well blew out back side. Dropped casing down and installed orbit valve to shut well in. Pumped 200 sax class A cement. Shut well in.
- 10-30-96 Well had gas pressure on it. Left well shut in until we could come up with drilling mud.
- 8-27-97 Bled gas pressure off well. Pumped 120 bbls. mud and 500 lbs. cotton seed hulls and 100 sax 60-40 pozmix with 3% cc., 4% gel. Let set for 1 1/2 hours. Open well up, a slight flow of gas. Mix another 100 sax 60-40 pozmix, 3% chloride, 4% gel. Pumped down well. Shut well in overnight.
- 8-28-97 Weak flow of gas. Pumped 100 sax class A cement with flow seal and 3% chloride. Waited 1/2 hour and well was dead. Put discharge hose down well and filled to surface. Cement stayed. Job complete.

944 0 11-28-96
107 SEP 14 11 48
LAWRENCE
LAWRENCE

LOCHIEL EXPLORATION INC., USA

1020 - 15th Street
Suite 41-C
Denver, Colorado 80202
(303) 825-0722

October 15, 1982

STATE RECEIVED
OCT 19 1982
KANSAS CORPORATION COMMISSION
Wichita, Kansas

Mr. Tom Leiker, Petroleum Proration Supervisor
Kansas Corporation Commission
200 Colorado Derby Building
Wichita, Kansas 67202

RE: ACO-1 Well History, CP-1
CP-4 Forms for 8 Wells in
Harper, Kingman & Reno Cos.

Dear Mr. Leiker:

Enclosed are two copies of the completion form and one set of logs for the following wells:

Lochiel Expl.	#1 Chase	Kingman Co.	C SE SW	24-28S-7W	
"	"	" "	C NW NE	7-28S-5W	
"	"	#1 Everett	Reno Co.	C SW SE	11-25S-6W
"	"	#1 Fry	" "	C NE NW	2-25S-5W
"	"	#1 Schrock	" "	SE NW SE	27-24S-5W
"	"	#1 McKinney	Harper Co.	C SE SW	20-33S-8W

These wells will all be produced as gas wells eventually, though at this time they have not connected to producing facilities.

Also enclosed are three copies of the completion forms with one set of logs, and one plugging form for the following wells:

Lochiel Expl.	#1 Harper	Kingman Co.	C SW NW	3-28S-7W
"	"	" "	C SW NE	9-27S-5W
	#1 Keiter			

We apologize for the delay in reporting the status of these last two wells. The Keiter forms were previously submitted, but returned due to being incomplete. Subsequently, several resignations of key personnel ensued. Only recently have the positions been filled and it was realized that the state requirements had not been satisfied. We hope you will understand these circumstances which resulted in the delay.

In checking with your office, ~~to discover~~ what forms you did not have, we learned that you had copies of the ~~ACO-1, CP-1 and CP-4~~ forms for the Lochiel #1 Wooldridge, C NW NE 14-27S-7W, Kingman County. Unfortunately, we are missing copies in our well file. Consequently, I wonder if we might impose upon you, to make a xerox copy of each form and send it to us.

Thank you.

Sincerely,

William H. Hawkins
W. H. Hawkins

WHH/amg