

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Edwards County, Sec. 9 Twp. 24 Rge. (E) 16 (W)

Location as "NE/CNW/SW" or footage from lines. SE SW NE/4

Lease Owner. M. B. Armer

Lease Name. Enlow Well No. 2

Office Address. 710 Petroleum Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry

Date well completed June 12, 1954

Application for plugging filed June 11, 1954

Application for plugging approved June 11, 1954

Plugging commenced June 11, 1954


Plugging completed June 12, 1954

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 3787 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	231'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy Rotary Mud to 220 ft.,  
set plug and cemented with 20 sacks - cement through  
drill pipe. Mudded hole to 35 ft., set plug and 10  
sacks cement at the surface.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 23 1954 6-23-54

CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor. Armer, Inc.

Address. Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.  
L. C. Sponenberg (employee of owner) or (well operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg

(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of June, 1954

Rose Lurey Notary Public.

My commission expires February 13, 1956.

24-7368-S 3-53-20M

PLUGGING  
FILE SEC 9 T 24 R 16W  
BOX PAGE 40 LINE 38

15-047-50017-0000

KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY M. B. Armer

SEC. 9 T. 24 R. 16W  
LOC. SE SW NE

FARM Enlow

NO. 2

TOTAL DEPTH 3787'

COUNTY Edwards  
KANSAS


COMM. 6-1-54

COMP. 6-12-54

SHOT OR TREATED

CONTRACTOR Armer, Inc.

ISSUED



CASING

20	10	
15	8	232'
12	6	
13	5	

ELEVATION 2076 K.B.

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

Clay	25
Sand	105
Shale & Shells	535
Sand	580
Red Bed & Gravel	720
Red Bed, Shale & Shells	1025
Anhydrite	1060
Red Bed & Shells	1280
Shale & Shells	1425
Shale & Lime	3110
Broken Lime	3210
Shale & Lime	3745
Lime	3787

FORMATION TOPS (K.B. Meas.)

ANHYDRITE	1025
HEEBNER	3601
TORONTO	3625
DOUGLAS	3644
BROWN LIME	3735
LANSING KANSAS CITY	3744

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

ARMER, INC.

RECEIVED BY  
STATE COMMISSION

STATE OF KANSAS

JUN 23 1954

SS:

6-23-54

COUNTY OF SEDGWICK

CONSERVATION DIVISION  
Wichita, Kansas

Subscribed and sworn to before me, a notary public, in and for said County and State this 22nd day of June, 1954.

*Rose Loney*  
Notary Public

My Commission expires February 13, 1956.

**PLUGGING**  
FILE SEC 9 T 24 R 16W  
BOOK PAGE 40 LINE 38