

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-21,209
LEASE NAME Campbell "B"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 3-18
SPOT LOCATION SW SW NW

LEASE OPERATOR F. G. Holl
ADDRESS 6427 East Kellogg
Wichita, Kansas 67207

SEC. 18 TWP. 24 SRGE. 16 (W)
COUNTY Edwards

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 5056

Date Well Completed 10-1-84
Plugging Commenced 7:00 AM,
10-7-84
Plugging Completed 8:30 AM,
10-7-84

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District No. 1

Is ACO-1 filed? If not, is well log attached? Yes

Producing formation Depth to top bottom T.D. 4430'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	256'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Filled hole with heavy mud,
plugged through open ended drill pipe 50 sacks at 1130'.
40 sacks at 600'; 50 sacks at 300', bridge, 1/2 sack hulls, plug and 10 sacks
at 40'. 15 sacks in rathole with joint of drill pipe. Pulled water well and
plugged with 5 sacks. Used 60/40 Pozmix, 2% gel and 3% cc.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142
Address P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

RECEIVED
STATE CORPORATION COMMISSION
10-12-84
OCT 12 1984

Harry J. Mead (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) Harry J. Mead
(Address) Harry J. Mead, Vice President
P. O. Box 129, Sterling, Kansas
67579



SUBSCRIBED AND SWORN TO before me this 8th day of October, 1984

Agnes D. Wurst
Notary Public

My Commission expires: 4-6-85

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- CAMPBELL "B" 3-18

Located: SW SW NW, Section 18-24S-16W, Edwards County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: October 1, 1984

COMPLETED: October 7, 1984

TOTAL DEPTH: 4430'

LOG

Casing Record

0 - 90 Surface Soil and Sand
 90 - 259 Shale and Clay
 259 - 830 Shale and Sand
 830 - 1122 Shale and Lime
 1122 - 1138 Anhydrite
 1128 - 4430 Lime and Shale

Ran 6 joints new 8 5/8", 23# casing.
 243.92' pipe set at 256' K.B. Cemented
 with 210 sacks 60/40 Pozmix, plus 3% cc.
 Plug down at 11:45 AM, 10-1-84, by
 Howco.

 Plugged.

Deviation Surveys: 1/4° at 2156'
 1 1/4° at 3476'

10-12-84
 RECEIVED
 STATE CORPORATION COMMISSION
 OCT 12 1984
 CONSERVATION DIVISION
 Wichita, Kansas