

API NUMBER 15-047-20,782-0000

LEASE NAME Campbell

WELL NUMBER B2-18

TYPE OR PRINT  
 NOTICE: Fill out completely and return  
 to Cons. Div. office within 30 days.

440 Ft. from SYN Line of Section (circle one)

440 Ft. from EW Line of Section (circle one)

LEASE OPERATOR EG Holl Co. LLC

SPOT LOCATION NW - NW - NW

ADDRESS PO Box 180167

SEC. 18 TWP. 24S S. RGE 16 (N) or (W)

CITY, STATE, ZIP Wichita, Ks. 67218-0167

COUNTY Edwards

PHONE# (316) 995-3171 OPERATORS LICENSE NO. 5056

Date Well Completed: \_\_\_\_\_

Character of Well D+A  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced 7-22-96

Date Plugging Completed 7-23-96

The plugging proposal was approved on 7-29-96 (date)

by Dodge City office - Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation(s) \_\_\_\_\_ Depth to Top PBTP 4354 T.D. 4417  
 -Bottom

Show depth and thickness of all water, oil and gas formations. Perfs: 4323-27.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
		0	250'	8 5/8	250'	0
		0	4412'	4 1/2	4412	2380'
						73 its.

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

7-22-96: Dumped 3-55gal drums of sand in well-dumped 45x. Cement on top of sand, after checking fillup. Top of sand at 4100'. (over)

7-23-96: Dia-log shot off csg. at 2380'- pulled csg - rigged down & moved off.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service Inc.

4-1-96

License No. 5893

Address PO Box 847 Pratt, Ks. 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: EG Holl LLC

STATE OF Kansas COUNTY OF Pratt

Judy Berry (Employee of plugging contractor or (operator) of above-described well, being first

duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) Pratt Well Service, Inc.

SUBSCRIBED AND SWORN TO before me this 30th day of July, 19 96

Kenneth W. Furgason  
 Notary Public

My Commission Expires: 6/19/00



RECEIVED  
 ANS CORP COMM  
 996  
 - 1 A 11: 03

Top hole: 300# hulls - 10 gal - 50 sx. cement - 10 gal - 100# hulls -  
8 1/2 plug - 150 sx. cement - 60/40 poz - 6% sel.

7-30-96

*[Faint, mostly illegible handwritten notes and bleed-through from the reverse side of the page.]*

KENNETH W. BUNCE  
Notary Public  
My Comm. Expires [illegible]