

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-21,366-0000

LEASE NAME Stapleton "B"

WELL NUMBER 2-23

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 23 TWP. 24S RGE. 17 ~~WEST~~(W)

COUNTY Edwards

Date Well Completed 12-10-90  
7:00 PM,

Plugging Commenced 12-10-90

8:15 PM  
Plugging Completed 12-10-90

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR F. G. Holl Company

ADDRESS P. O. Box 780167  
Wichita, Kansas 67277-0167

PHONE# (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well Dry Hole

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-10-90 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed?            If not, is well log attached? Yes

Producing Formation            Depth to Top            Bottom            T.D. 4530'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	312'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.

Fill hole with heavy mud. 50 sasks at 2000'; 40 sasks at 1000'; 40 sasks at 500';  
40 sasks at 350'; 10 sasks and plug at 40'. 10 sasks in mousehole and 15 sasks in  
rathole. Used 60/40 Pozmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor STERLING DRILLING COMPANY License No. 5142

Address P. O. Box 129  
Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

Harry J. Mead (Employee of Operator) or (Operator) of  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,  
statements, and matters herein contained and the log of the above-described well as filed that  
the same are true and correct, so help me God.

(Signature) Harry J. Mead  
Harry J. Mead, Vice President  
(Address) P. O. Box 129, Sterling, Kansas 67579

12-13-90  
DEC 1 1990

SUBSCRIBED AND SWORN TO before me this 12th day of December, 1990



AGNES D. WURST  
State of Kansas  
My Appt. Exp. 4-26-93

Wichita, Kansas

Agnes D. Wurst  
Agnes D. Wurst, Notary Public

My Commission Expires: 4-26-93

# STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - STAPLETON "B" #2-23

Located: C NW SE, Section 23-24S-17W, Edwards County, Kansas

OWNER: F. G. Holl Company

DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: December 4, 1990

COMPLETED: December 10, 1990

TOTAL DEPTH: 4530'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 70 Surface Soil and Sand	Ran 7 joints 8 5/8" OD casing.
70 - 160 Sand and Red Bed	298.88' pipe set at 312' K.B.
160 - 315 Shale	Cemented with 225 sacks 60/40 Pozmix, 2% gel and 3% cc. Plug down at 7:00 PM, 12-4-90, by B. J. Titan.
315 - 1175 Lime and Shale	
1175 - 1190 Anhydrite	
1190 - 1245 Lime and Shale	
1245 - 1870 Shale, Salt, Lime Str.	
1870 - 4530 Lime and Shale	Plugged.

STATE CORPORATION COMMISSION  
BY THE SECRETARY OF

DEC 1 1990 12-13-90

Deviation Survey: 1° at 4394'

CONSERVATION DIVISION  
Wichita, Kansas