

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Edwards County. Sec. 23 Twp. 24S Rge. 17W E2W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
NW NW NW

Lease Owner F. G. Holl, et al.
Lease Name Frohling #1-23 Well No. 1-23

Office Address P. O. Box 129, Sterling, Kansas 67579
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole


Date Well completed May 5, 1978 19
Application for plugging filed May 4, 1978 19
Application for plugging approved May 4, 1978 19
Plugging commenced 8:00 AM, May 5, 1978 19
Plugging completed 10:45 AM, May 5, 1978 19
Reason for abandonment of well or producing formation

Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation Depth to top Bottom Total Depth of Well 4560'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | FEET IN | PULLED OUT |
|-----------|---------|------|----|--------|---------|------------|
| | | | | 8 5/8" | 252' | None |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud. 5-9-78
Pumped through open ended drill pipe
40 sacks at 540' and 40 sacks at 240';
solid bridge at 40' with plug and 1/2
sack hulls and 12 sacks to surface; STATE CORPORATION COMMISSION
3 sacks in rathole. Used 50/50 Pozmix. MAY 09 1978

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company
P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE

F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

Subscribed and sworn to before me this 8th day of May 1978

My commission expires CHARLES M. HALL
Rice County, Ks.
My Appt Exp. Jan 31, 1982

Charles M. Hall, Notary Public

15-047-20377-0000

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- FROHLING #1-23
Located: NW NW NW, Section 23-24S-17W, Edwards County,
Kansas

OWNER: F. G. Holl, et al
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: April 27, 1978
COMPLETED: May 5, 1978

TOTAL DEPTH: 4560'

LOG

0 - 255 Sand, Clay and Shale
255 - 575 Red Bed and Shale
575 - 1057 Sand and Red Bed
1057 - 1098 Red Beds
1098 - 1118 Anhydrite
1118 - 1400 Shale
1400 - 2110 shale and Lime Strs.
2110 - 4335 Lime and Shale
4335 - 4362 Cherty (Cong.)
4362 - 4455 Chert and Lime
4455 - 4560 Cherty Lime and Shale

CASING RECORD

Ran 6 joints used 28#, 8 5/8" casing,
240.34' set at 252' K.B. with 225 sacks
60/40 Pozmix with 3% cc. Plug down at
12:30 PM, 4-27-78, by Howco.

Plugged.

5-9-78
RECEIVED
STATE COMMISSIONER OF GEOL. & MINES

MAY 09 1978