

15-047-20704-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Edwards County, Sec. 23 Twp. 24S Rge. 17W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
NW NW NE/4 (330' FWL; 330' FNL)

Lease Owner F. G. Holl  
Lease Name King #2-23 Well No. 2

Office Address 6427 East Kellogg, Wichita, Kansas 67207  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Dry Hole

Date Well completed July 5, 1980 19  
Application for plugging filed July 4, 1980 19  
Application for plugging approved July 4, 1980 19  
Plugging commenced 12:30 AM July 5, 1980 19  
Plugging completed 2:30 AM July 5, 1980 19  
Reason for abandonment of well or producing formation \_\_\_\_\_


Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4470'

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	268'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud.  
Heavy mud plugged through open drill pipe;  
40 sacks at 600'; 40 sacks at 240';  
heavy mud, bridge with hulls and plug,  
10 sacks at 40'; 5 sacks in rathole.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 16 1980

(If additional description is necessary, use BACK of THIS SHEET, Kansas

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.  
F. A. Wuellner (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
F. A. Wuellner, Secretary  
P. O. Box 129, Sterling, Kansas 67579  
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of July, 1980.



[Signature]  
Charles M. Hall, Notary Public.

My commission expires \_\_\_\_\_

15-047-20704-0000

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG ----- KING #2-23  
Located: NW NW NE/4 (330' FWL; 330' FNL), Section 23-24S-17W,  
Edwards County, Kansas

OWNER: F. G. Holl  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: June 27, 1980  
COMPLETED: July 5, 1980

TOTAL DEPTH: 4470'

<u>LOG</u>	
0 - 101	Sand and Surface
101 - 346	Shale
346 - 1114	Shale, Red Bed, Sand
1114 - 1128	Anhydrite
1128 - 1823	Shale
1823 - 3780	Lime and Shale
3780 - 4225	Lime
4225 - 4348	Lime and Shale
4348 - 4372	Miss. Chert
4372 - 4400	Chert and Lime
4400 - 4470	Lime and Shale

CASING RECORD

Ran 6 joints used 28#, 8 5/8" OD casing.  
255.99' set at 268' K.B. Cemented with  
225 sacks 60/40 Pozmix with 3% cc. Plug  
down at 2:00 PM, 6-27-80, by Howco.

Plugged.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 16 1980  
CONSERVATION DIVISION  
Wichita, Kansas

Deviation Surveys: 1° at 1823'  
2° at 4372'