

STATE OF KANSAS
STATE CORPORATION COMMISSION
220 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-047-00031-0001
API NUMBER

LEASE NAME Brasfeild #1

WELL NUMBER

SPOT LOCATION NE SE NW

SEC 20 TWP. 24 RGE. 16 (E) or (W)

COUNTY Edwards

Date Well Completed

Plugging Commenced 7/17/84

Plugging Completed 7/23/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F.G. Holl

ADDRESS 6427 E. Kellogg, Wichita, Ks. 67208

PHONE # () OPERATORS LICENSE NO. 5056

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4403'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	208'	none
				4 1/2"	4402'	2107'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pumped bottom with 35 sacks cement to 4000'. Shot pipe at 3519', 3224', 3027', 2812', 2723', 2510', 2313', & 2107'. Pulled 49 joints. Plugged surface with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, released plug & displaced with 125 sacks 50/50 poz 2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, KS. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God. STATE CORPORATION COMMISSION

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

AUG 01 1984

CONSERVATION DIVISION
Wichita, Kansas
SUBSCRIBED AND SWORN TO before me this 31st day of July, 1984



Irene Hoover
Notary Public

My Commission expires: