

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Edwards County. Sec. 30 Twp. 24 Rge. (E) 16 (W)

Location as "NE/CNW/SW" or footage from lines C SW SE

Lease Owner DONALD C. SLAWSON

Lease Name Breitenbach 'A' Well No. 1

Office Address 408 One Twenty Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 11/5-65

Application for plugging filed 11/5-65

Application for plugging approved 11/5-65


Plugging commenced 11/5-65

Plugging completed 11/5-65

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well A. Elving, Box 248, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4469 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 250', set plug, 1/3 sack hulls,
25 sacks regular cement, mud to 40',
set plug, 10 sacks regular cement,
2 sacks regular cement in rat hole

RECEIVED
NOV 15 1965
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Slawson Drilling Company, Inc.

Address 408 One Twenty Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

DONALD C. SLAWSON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

408 One Twenty Building, Wichita, Ks. (Address)

SUBSCRIBED AND SWORN TO before me this 12th day of November, 1965

My commission expires August 25, 1968

[Signature]
Ella Priess

Notary Public.

15-047-30061-0000

WELL LOG

Company: DONALD C. SLAWSON
 408 One Twenty Building
 Wichita, Kansas

Farm: Breitenbach 'A' #1
 C SW SE, Section 30-24S-16W
 Edwards County, Kansas

Total Depth: 4469' Elev. 2094 K.B.

Commenced: October 23, 1965
 Completed: November 4, 1965

Contractor: Slawson Drilling Co., Inc.

Casing: 8 5/8" @ 276' with 285 sacks of cement

0-85	Sand & Gravel
85-1575	Shale & Shells
1575-1765	Shale
1765-1900	Shale & Shells
1900-2075	Salt - Shale
2075-2760	Lime
2760-3844	Lime & Shale
3844-4346	Lime
4346-4360	Lime & Chert
4360-4365	Lime
4365-4375	Chert & Lime
4375-4390	Lime & Chert
4390-4469	Lime & Shale


RECEIVED
 STATE CORPORATION COMMISSION
 NOV 17 1965
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
)SS:
 COUNTY OF SEDGWICK)

I, Donald C. Slawson, of the Slawson Drilling Company, Inc., upon oath state that the above and foregoing is a true and correct copy of the log of the Breitenbach 'A' #1 well.


 DONALD C. SLAWSON

Subscribed and sworn to before me this 8th day of November, 1965.


 Ella Priess, Notary Public

My Commission Expires:
 August 25, 1968