

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Edwards SEC. 35 TWP. 24 RGE. 16 ~~XX~~W
 Location as in quarters or footage from lines:
S/2/N/2/SW

Locate Well
 correctly on above
 Section Platt.

Lease Owner Herndon Oil & Gas Company
 Lease Name Kearney Well No. #2
 Office Address R. R. #2 - Box 20 - Arkansas City, Ks.
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced October 27, 1982
 Plugging completed November 4, 1982
 Reason for abandonment of well or producing formation
Depleted

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz
 Producing formation _____ Depth to top _____ bottom _____ T.D. 4398'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	357'	NONE
				4 1/2"	4397'	2520.03

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Dumped sand to 4250' and four (4) sacks cement.
 Shot pipe @ 3700', 3500', 3000' and 2500'.
 Pulled seventy-four (74) joints 4 1/2" casing.
 Squeezed well with three (3) sacks hulls, twenty (20) sacks gel,
 seventy (70) sacks 50/50 pozmix cement with 4% added gel and
 3% calcium chloride, one (1) hulls and fifteen (15) gel.
 Released plug and pumped one hundred (100) sacks cement.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the

above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
 JAMES W. ROCKHOLD - Box 698 - Great Bend, Ks.
 (Address) 67530

SUBSCRIBED AND SWORN TO before me this 18th day of Nov., 1982



My Commission expires _____

Margaret Prosser
 RECEIVED Notary Public.
 STATE CORPORATION COMMISSION

NOV 22 1982 11-22-82

CONTRACTOR'S WELL LOG

OPERATOR:	Herndon Oil and Gas Company
CONTRACTOR:	Union Drilling Co., Inc.
LEASE NAME:	Kearney #2
LOCATION:	C S/2 N/2 SW/4 Section 35-24S-16W Edwards County, Kansas
COMMENCED:	November 21, 1979
COMPLETED:	November 30, 1979

0	2005	Shale	Set 8 5/8" @ 357' w/275 sacks
2005	2341	Shale and lime	
2341	2580	Shale	
2580	4410	Lime and shale	

We certify that the above and foregoing is a true and correct copy of the log on the Kearney, C S/2 N/2 SW/4 Section 35-24S-16W, Edwards County, Kansas.

Union Drilling Co., Inc.

R. D. Messinger

 R. D. Messinger

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Suscribed and sworn to before me, a Notary Public, in and for the aforesaid County and State as of this 26th day of November, 1979.

My appointment expires;

11-6-82

Cynthia L. Roney

 Cynthia L. Roney-Notary Public



RECEIVED
 STATE CORPORATION COMMISSION
 SEP 22 1982
 CONSERVATION DIVISION
 Wichita, Kansas