



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

August 5, 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

RECEIVED
 STATE CORPORATION COMMISSION

AUG 13 1963
 8-13-63
 CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Joe Rohling of Skelly Oil Company has this

date requested permission to plug the following described well:

Mr. Rohling guarantees payment of the plugging fee.

Operator's full Name: Skelly Oil Company

Complete Address: P.O. Box 7, Cunningham, Kansas

Lease Name: W. A. Gossage Well No. 1

Location: C SW SE Sec. 17 Twp. 22 Rge. 7 (E) (W) X

County Reno Total Depth 3950' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rohling was instructed to plug the well as follows:

Fill hole with mud to 350'. Push plug and 1/2 sack hulls to
350' and cement with 20 sacks through drill pipe. Fill
hole with mud to 35'. Push plug and 1/2 sack hulls to 35'
and cap hole with 10 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,

[Signature]
 Conservation Division Agent