



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

August 15, 1973

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 20 1973
CONSERVATION DIVISION
Wichita, Kansas

8-20-73

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Harold Brown of Trans America Oil Corporation has this date requested permission to plug the following described well:

Mr. Brown guarantees payment of the plugging fee.

Operator's full Name: Trans America Oil Corporation

Complete Address: 23 W Second, Hutchinson, Kansas

Lease Name: Hungerford (Now Halling) Well No. 1

Location: C SE NW Sec. 20 Twp. 22 Rge. 7 (E) (W) X

County: Reed Total Depth 3532 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Brown was instructed to plug the well as follows:

Fill hole with mud to 240'. Push plug and 1/4 sack hulls to 240' and cement hole with 25 sacks cement through drill pipe. Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

W. L. J. Loman
Conservation Division Agent